

BRUHATH BENGALURU MAHANAGARA PALIKE, DASARAHALLI ZONE
Office of Executive Engineer
SCHEDULE -B

Name Of Work :Improvemnts to road and drains at abbigere layout in ward no.12 Shettyhalli Sub Division					
Sl.No	Description of Work	Unit	Qty	Sanctioned Rate	
				In Figures (Rs.)	In Words (Rs.)
1	Earthwork excavation by manual means in ordinary soil involving in average horizontal throw up to 2m & an average lift upto 1.5m , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per specifications.	Cum	691.20	79.63	Seventy Nine and Sixty Three Paise
2	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	cum	92.70	4854.52	Four Thousand Eight Hundred Fifty Four and Fifty Two
3	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal, coarse aggregate @ 0.69 cum and fine aggregates @ .460cum, with super plasticisers @ 3 liters confirming to is 9103-1999 reaffirmed - 2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings, pedestals, retaining walls, staircase, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications.	Cum	260.22	6062.89	Six Thousand Sixty Two and Eighty-Nine Paise
4	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth cills and string courses cost of all materials, labour complete as per specifications.	sqm	1739.70	239.38	Two Hundred Thirty Nine and Thirty Eight Paise
5	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	Tonne	15.80	66067.5	Sixty Six Thousand Sixty Seven and Fifty Paise

[Signature]
EXECUTIVE ENGINEER
Bruhat Bangalore Mahanagara Palike
Dasarahalli Division, Bangalore-560057

6	Providing & laying reinforced cement precast slabs of mix CC 1:1 1/2:3 using 20mm & down size graded Granite metal using HYSD 10mm dia steel @ 100mm c/c both ways & Complete as per specifications.	Sqm	562.50	1777.12	One Thousand Seven Hundred Seventy Seven and Twelve Paise
---	--	-----	--------	---------	---


Signature of Contractor


Executive Engineer
Dasarahalli Division



rtificat
rtifica
sou
iq
in
e

EXECUTIVE ENGINEER
Bulandshahr District
Bulandshahr District